BENGALURU WEST CITY CORPORATION

TENDER DOCUMENT
(KW-2)

(Excluding GST)

Beautification Maintenance Horticulture Works and Other Emergency Works
Estimated Cost: Rs.25,00,000/-
(Amount Put to Tender Rs. 21,18,025/- is Excluding GST)

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

TENDERS FOR THE WORK OF: **:** Beautification Maintenance Horticulture Works and Other Emergency Works

TENDER REFERENCE : No: SADH(W-2)TENDER/07/2025-26

Dated:26.02.2026

PERIOD OF SALE OF TENDER DOCUMENT : View kppp.karnataka.gov.in Portal
I

LAST DATE FOR SALE OF TENDER DOCUMENT : View kppp.karnataka.gov.in Portal

LAST DATE AND TIME FOR RECEIPT OF TENDERS : View kppp.karnataka.gov.in Portal

PRE TENDERS MEETING : View kppp.karnataka.gov.in Portal

TIME AND DATE OF OPENING OF TENDERS **:** **View kppp.karnataka.gov.in Portal**

PLACE OF OPENING OF TENDERS } Senior Assistant Director of Horticulture Bengaluru West City Corporation Zone-2, Malleshwaram, No-98, 8th Cross, Malleshwaram, Bangalore-

ADDRESS FOR COMMUNICATION }

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Contents

Section No.	Description	Page
1	INVITATION FOR TENDERS (IFT)	3
2	INSTRUCTIONS TO TENDERERS (ITT)	4
3.	FORM OF TENDER AND QUALIFICATION INFORMATION	13
4.	CONDITIONS OF CONTRACT (CC)	18
5	CONTRACT DATA	29
6	SPECIFICATIONS	31
7	DRAWINGS	32
8.	BILL OF QUANTITIES	33

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

SECTION 1: INVITATION FOR TENDERS (IFT)

BENGALURU WEST CITY CORPORATION

Senior Assistant Director of Horticulture Bengaluru West City Corporation
Zone-2, Malleshwaram, No-98, 8th Cross, Bangalore-560003

No: SADH(W-2)TENDER/07/2025-26
Dated:26.02.2026

LETTER OF INVITATION FOR TENDER(IFT)

(SHORT TERM)
(SINGLE & TWO COVER SYSTEM)
(Through **kppp.karnataka.gov.in portal** only)

A) The Senior Assistant Director of Horticulture (West-2), (Referred to as Employer in these documents) invites tenders to Implement in accordance with KTPP rules 2000, from eligible and experienced Person/Agencies / Firms (Referred to as Tenderers in these documents) registered in Labour department for Beautification, Maintenance Development of Works.

B) The tenderers are advised to note the minimum qualification criteria specified in Clause 3 of the instructions to tenderers to qualify for award of the contract (standard tender document KW-2)

C) Tender documents may be downloaded from Government of Karnataka e-Procurement website **https://kppp.karnataka.gov.in/#/portal/portal-home** under login for Contractors.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

D) After login to Contractors, Please scroll down to the left side bottom to see List of Tenders, Please click there to find the details of NIT & download copy of the tender. The tender can be downloaded in the portal as per prescribed date and time published in the portal. Only Interested Tenderer who wish to participate should remit on line transaction fee for tender after registering in the portal. The transaction fee is non-refundable.

E) Tenders must be accompanied by earnest money deposit (EMD) specified for the work in the table below. EMD will have to be submitted online through website **https://kppp.karnataka.gov.in.**

F) Tenders must be electronically submitted (online) within the date and time published in e-procurement portal. Tenders will be opened at prescribed time and date in the e-procurement portal, in the presence of the Tenderers who wish to attend in the Office of The Senior Assistant Director of Horticulture, Bengaluru West City Corporation Zone-2, Malleshwaram, Bangalore.

G) Tenderers are subjected to the provisions of KTPP (Amendment) Rules 2017 and selected works in Randomization shall be reserved for participation by tenderers belonging to the scheduled castes & scheduled tribes.

H) Tender conditions shall be followed as per KWs

TABLE

Sl no	Name of the work	Total Estimated Cost Rs. In Lakhs	Total Estimated Cost Rs. In Lakhs (Excluding GST)	EMD Amount (in Rs)	Stipulated period of Completion (in months)	Category	
1	Beautification Maintenance Horticulture Works and Other Emergency Works	25.00	21.18	50000	03 Months	Others	KW-2

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Calendar of events as follows:

- Date of Notification : 26.02.2026
- Tender can be downloaded from : 02.03.2026
- Pre bid meeting date : 05.03.2026 at 11.00 AM
- Tender Closing Date : 09.03.2026 at 4.30 PM
- Technical bid opening date : 11.03.2026 at 4.30 PM
- Financially bid opening date : After Approval of Technical bid.

Note:

Aspiring Bidders/contractors who have not registered in e – procurement should register before participating through the website https://kppp.karnataka.gov.in

a. Before submission of online bids, bidders must ensure that scanned copies of the necessary documents been attached with bid.
b. All the required information required bids must be filled and submitted online.
c. For details, registration and e- payment visit GOK e-procurement website. https://kppp.karnataka.gov.in or contact e- procurement Helpdesk at 080-22371090, 22373788.
d. This tender notice can also be seen on the Website Greater Bengaluru Authority (www.bbmp.gov.in)
e. Any other details regarding the above work/service and other information obtained from the above office during office hours.

Sd/-

Senior Assistant Director of
0Horticulture

6

Senior Assistant Director of
Horticulture
Bengaluru west City
Corporation
Zone-2, Malleshwaram

Bengaluru West

City Corporation

Zone-2,

Malleshwaram

Copy Submitted to:-

1. The Commissioner (BWCC) for kind information
2. The Additional Commissioner (Development) BWCC for kind information
3. Chief Engineer BWCC Zone-2 for kind information
4. Deputy Controller Finance (BWCC) for information
5. The Public Relation Officer, BWCC
6. Office Notice Board

Senior Assistant

Director of Horticulture

Bengaluru West City

Corporation

Zone-2,

Malleshwaram

SECTION 2: INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

A.	**General**		**Page No.**
	1.	Scope of Tender	10
	2.	Eligible Tenderers	10
	3.	Tender capacity	10
B.	**Tender Documents**		
	4.	Content of Tender documents	11
	5.	Amendment of Tender documents	11
C.	**Preparation of Tenders**		

7

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

6. Documents comprising the Tender 11
7. Tender prices 11
8. Tender validity 12
9. Earnest money deposit 12
10. Format and signing of Tender 12

D. Submission of Tenders

11 Sealing and marking of Tenders 12
12 Deadline for submission of Tenders 13
13 Late Tenders 13
14 Modification and Withdrawal of Tenders 13

E. Tender opening and evaluation

15. Tender opening 13
16. Process to be confidential 14
17. Clarification of Tenders 14
18. Examination of Tenders and determination of responsiveness 15
19. Correction of errors 15
20. Evaluation and comparison of Tenders 15

F. Award of contract

21. Award criteria 15
22 Employer's right to accept any Tender and to reject any or all Tenders 15
23. Notification of award and signing of Agreement 15
24. Security deposit 16
25. Corrupt or fraudulent practices 16

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

A. General

1. Scope of Tender

1.1 The Senior Assistant Director of Horticulture (West-2), invites tenders from Contractors any state or Central Govt. Organization for the above tender work (as defined in these documents and referred to as "the works") detailed in the Table given in the Invitation for Tenders (IFT). The tenderers may submit tenders for the **work of Beautification Maintenance Horticulture Works and Other Emergency Works detailed in the table given in BOQ.**

2. Eligible Tenderers

2.1

a. For general category works:

I) Tenderer should submit work done certificate of at least one similar work (Beautification, Maintenance Development of Works in Parks) to an extent of 50% of the total tendered amount during last five financial years (i.e 2020-2021,2021-22,2022-23, 2023-24 & 2024-25) of its work. The work done certificate should duly certified by the competent authorities (Central Govt/State Govt / Govt Boards / Govt Corporation). **Work done certificate will not be considered if Work carried through contract labour.**

b. For Scheduled Caste & Scheduled Tribes reserved works:

Tenderer should submit work done certificate of at least one similar (Beautification, Maintenance Development of Works in Parks) to an extent of 25% (6,25,000/-)of the total tendered amount during last five financial years (i.e 2020-2021,2021-22,2022-23, 2023-24 & 2024-25) of its work. The work done certificate should duly certified by the competent authorities (Central Govt/State Govt / Govt Boards / Govt Corporation). **Work done certificate will not be considered if Work carried through contract labour.**

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

d. For general category works: Achieved in at least two financial years a minimum financial turnover of **Rs.50,00,000/- (usually not less than two times the estimated** annual payment under this contract) during last Three financial years (i.e 2022-23, 2023-24 & 2024-25) attested by the Chartered Accountant with UDIN Number.

e. For Scheduled Caste & Scheduled Tribes reserved works:

Achieved in at least One financial year a minimum financial turnover of Rs.50,00,000/- (**usually not less than two times the estimated**annual payment under this contract) during last Three financial years (i.e 2022-23, 2023-24 & 2024-25) attested by the Chartered Accountant with UDIN Number.

f. The Tenderer should submit valid Labour Department License, P.F & ESI registration Certificate, ESI and EPF Payment Challans of Latest months, ITR with Acknowledgement of Last Two Years (Assessment Year 2023-24, 2024-25) & TDS Annual Certificate (26 AS) (Last 2 Years i.e. Financial Year 2023-24 & 2024-25) (26AS), valid PAN card and GST registration Certificate copies and GST returns 3B Paid Challans of Latest 6 Months(June-2025 to December-2025) along with tender document. Contractor shall fully comply provisions of various applicable labour laws provisions of the following enactments and other enactments as applicable for such contracts.

- Contract Labour (R&A) Act 1970 and rules 1971.
- Payment of Wages Act.
- Minimum Wages act 1948, Karnataka Rules 1952
- Employees State Insurance Act 1948, Rules and regulations 1950
- Employees Provident Fund Act 1952 and Pension Scheme 1995
- Karnataka Shops and Commercial Establishment Act 1961

i) As per the Employees' State Insurance Act, 1948 (ESI Act), the employer is responsible for registering the employees and paying the ESIC contribution for them. In this case, the contractor is the employer of the labourers and is responsible for registering them and paying their ESIC contribution. Hence your hereby advised to

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

submit the latest 6 Months (June-2025 to December-2025) ESIC Statement and Paid Challan Details along with Registration Certificate in Form C-11 of the Act.

ii) As per the Employees' Provident Funds and Miscellaneous Provisions Act, 1952 (EPF Act), the employer is responsible for registering the employees and paying the Provident Fund (PF) contribution for them. In this case, the contractor is also responsible for registering the labourers and paying their PF contribution. (latest 6 Months June-2025 to December-2025) ECR & PF Paid Challan Details along with Registration Certificate) Any establishment employing even less than 20 persons can be covered voluntarily u/s 1(4) of the Act.

e. Tenderers applying for reserved tenders must furnish the documentof caste certificate and **DOMICILE CERTIFICATE**(**Residential Certificate is not acceptable**) as per Finance Department Letter dated: 13.08.2019) as per GOK order

2.2 **Tenders from Joint ventures are not acceptable.**

3. Tender capacity:

3.1 **Assessed available tender capacity = (A*N*1.5 - B)**
where

A = Maximum value of Horticulture Landscape Development works executed in any one year during the last five years

N = Number of years prescribed for completion of the works for which tenders are invited.

B = Value, at ———— (price level), of existing commitments and on-going works to be completed during the year

Note: The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by that particular tender calling authority.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

3.2 Even though the tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.
- Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by the Government of Karnataka and The Contractor should not involve in any of the criminal offense.
- All Xerox Documents uploaded by the bidder should be attested by notary.

B. Tender documents

4. Content of Tender documents

4.1 The set of tender documents shall have all the Sections given in Page 2:
4.2 NA

5. Amendment of Tender documents

5.1 Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.
5.2 Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.
5.3 To give prospective tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 12.2 below.

6. Site visit:

6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for Beautification, Maintenance Development of Works. The cost of visiting the Site shall be at the Tenderer's own expense. And any clarification and suggestions regarding work execution will be cleared in the site itself to the Tenderer, during the time of visit along with the tender inviting authority and the same, site inspection report issued by the TIA should be submitted along with the technical bid document.

C. Preparation of Tenders

6. Documents comprising the Tender

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

6.1 The tender submitted by the Tenderer shall comprise the following:
(a) The Tender (in the format indicated in Section 3).
(b) Priced Bill of Quantities;
(d) Qualification Information Form and Documents;
and any other materials required to be completed and submitted by tenderers in accordance with these instructions. **The documents listed under Sections 3, 5 and 8 shall be filled in without exception.**

7. Tender prices

7.1 The contract shall be for the whole works as described in Sub-Clause 1.1, based on the priced Bill of Quantities submitted by the Tenderer.

7.2 The Tenderer shall fill in rates and prices and line item total (both in figures and words) for all items of the Works described in the Bill of Quantities along with total tender price (both in figures and words). *Items for which no rate or price is entered by the Tenderer will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities.* Corrections, if any, shall be made by crossing out, initialing, dating and rewriting.

7.3 All duties, taxes, and other levies payable by the contractor under the contract, or for any other cause, shall be included in the rates, prices and total Tender Price submitted by the Tenderer.

7.4 The rates and prices quoted by the Tenderer shall be fixed for the duration of the Contract and shall not be subject to adjustment on any account.

8. Tender validity

8.1 Tenders shall remain valid for a period not less than 180 days after the deadline date for tender submission specified in Clause 12. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.

8.2 In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the tenderers may extend the period of validity for a specified additional period. The request and the tenderers' responses shall be made in writing or by cable. A tenderer may refuse the request without forfeiting his earnest money deposit. A tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 9 in all respects.

9. Earnest money deposit

9.1 EMD amount as % of the estimated cost of the work put to tender

a) Upto Rs.20 lakh – 2.5% (Reservation Category Works 1.25%)

b) Rs.20 lakh and above upto Rs.1 crore – 2% subject to a minimum of Rs.50,000/-

(Reservation Category Works 1% subject to a minimum of Rs.25,000/-)

c) Rs.1 crore and above upto Rs.10 crore – 1.5% subject to a minimum of Rs.2,00,000/-

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

d) Rs.10 crore and above - 1% subject to a minimum of Rs.15,00,000/-

9.2 NA.
9.3 NA.
9.4 NA
9.5 NA
9.6 NA

10. Format and signing of Tender

10.1 NA
10.2 NA
10.3 NA.

D. Submission of Tenders

11. Sealing and marking of tenders

Tenderer shall submit the Tender document electronically before the submission date and time published. The document for submission shall be uploaded in PDF format and submitted in the order mentioned below**.**

1. Content sheet with name of folder / file, No of pages in each folder / file and size of the folder/file.

FIRST COVER /FOLDER (TECHNICAL PART)

2. As per Section 3 - Qualification information (Reffer Annexure 3)

a. Qualification information summary sheets

b. Affidavit as per the format attached in qualification information.

c. Brief description of tenderer with the details of contact person for communication with BWCC

d. Attested copy of Registration certificate of the contractor

e. NA

f. Experience & qualification of key persons as per Table 5 of qualification information.

g. Line of credit and details of tenderer's bank with reference as per format attached in qualification information.

h. NA

i. NA

SECOND COVER/FOLDER (FINANCIAL PART)

a. Form of tender as per section 4 (I) of tender document.
b. Priced Bill of Quantity.
c. Any other materials required to be completed and submitted by Tenderers in accordance with ITT.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

12. Deadline for submission of the Tenders

12.1 In online e-procurement system, tenderer shall not be able to submit the bid after the bid submission time and date as the icon or the task in the e-procurement portal will not be available.

12.2 The Employer may extend the deadline for submission of tenders by issuing an amendment in accordance with Clause 5, in which case all rights and obligations of the Employer and the Tenderers previously subject to the original deadline will then be subject to the new deadline.

13. Late Tenders

13.1 In online e-procurement system, you shall not be able to submit the bid after the bid submission time and date as the icon or the task in the e-procurement portal will not be available.

14. Modification and Withdrawal of Tenders

14.1 Tender has all the time to modify and correct or upload any relevant document in the portal till Bid submission date and time, as published in the e-procurement portal.

E. Tender opening and evaluation

15. Opening of First Cover of all Tenderers and evaluation to determine qualified Tenderers:

15.1 The Employer will open online the First Covers of all the Tenders received through e-procurement portal, in the presence of the Tenderers or their representatives who choose to attend on the date and the place specified in the e-procurement portal. In the event of the specified date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

15.2 NA

15.3 NA

1 5.4 The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 15.3.

16. Process to be confidential

16.1 Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.

17. Clarification of Tenders

17.1 To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the Tenders in accordance with Clause 19.

17.2 Subject to sub-clause 17.1, no Tenderer shall contact the Employer on any matter relating to its Tender from the time of the Tender opening to the time the contract is awarded. If the Tenderer wishes to bring additional information to the notice of the Employer, it should do so in writing.

17.3 Any effort by the Tenderer to influence the Employer in the Employer's Tender evaluation, Tender comparison or contract award decisions may result in the rejection of the Tenderers' Tender.

18. Examination of Tenders and determination of responsiveness

18.1 A substantially responsive Tender is one which conforms to all the terms, conditions, and specifications of the Tender documents, without material deviation or reservation. A material deviation or reservation is one (a) which affects in any substantial way the scope, quality, or performance of the Works; (b) which limits in any substantial way, inconsistent with the Tender documents, the Employer's rights or the Tenderer's obligations under the Contract; or (c) whose rectification would affect unfairly the competitive position of other Tenderers presenting substantially responsive Tenders.

18.2 If a Tender is not substantially responsive, it will be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

19. Correction of errors

19.1 Tenders determined to be substantially responsive will be checked by the Employer for any arithmetic errors. Errors will be corrected by the Employer as follows:

(a) where there is a discrepancy between the rates in figures and in words, the lower of the two will govern; and

(b) where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern.

19.2 The amount stated in the Tender will be adjusted by the Employer in accordance with the above procedure for the correction of errors and, with the concurrence of the Tenderer, shall be considered as binding upon the Tenderer. If the Tenderer does not accept the corrected amount the Tender will be rejected,

20. Evaluation and comparison of Tenders

20.1 The Employer will evaluate and compare only the Tenders determined to be substantially responsive in accordance with Clause 18.

20.2 In evaluating the Tenders, the Employer will determine for each Tender the evaluated Tender Price by adjusting the Tender Price as follows:

(a) making any correction for errors pursuant to Clause 19; and

(b) making appropriate adjustments to reflect discounts or other price modifications offered in accordance with Sub Clause 14.5.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

20.3 The Employer reserves the right to accept or reject any variation, deviation, or alternative offer. Variations, deviations, and alternative offers and other factors which are in excess of the requirements of the Tender documents or otherwise result in unsolicited benefits for the Employer shall not be taken into account in Tender evaluation.

F. Award of Contract

21. Awardcriteria

21.1 Subject to Clause 22, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be (a) eligible in accordance with the provisions of Clause 2, and (b) qualified in accordance with the provisions of Clause 3.

22. Employer's right to accept any Tender and to reject any or all Tenders

22.1 Notwithstanding Clause 21, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds for the Employer's action.

23. Notification of award and signing of Agreement

23.1 The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex or facsimile confirmed by registered letter. This letter (hereinafter and in the *Conditions ofContract* called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").

23.2 The notification of award will constitute the formation of the Contract, subject only to the furnishing of a performance security in accordance with the provisions of Clause 24.

23.3 The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer within 07 days following the notification of award along with the Letter of Acceptance. Within 07 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.

23.4 Upon the furnishing by the successful Tenderer of the Security deposit, the Employer will promptly notify the other Tenderers that their Tenders have been unsuccessful.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

24. Security deposit

24.1 Within 07 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security Deposit by Bank Guarantee in favour of Chief Commissioner BWCC payable at Bengaluru**for an amount equivalent to 5% of the Contract price and difference amount in the form of Bank Guarantee(saperately)** in favour of Chief Commissioner BWCC payable at Bengalore

24.2 NA

24.3 Failure of the successful Tenderer to comply with the requirements of Sub-Clause 24.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the earnest money deposit.

25. Corrupt or Fraudulent practices

25.1 The BWCC requires that the Tenderers, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, BWCC:

(a) will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;

(b) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a BWCC contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a BWCC contract.

25.2 Furthermore, Tenderers shall be aware of the provision stated in sub-clause 43.2 of the Conditions of Contract.

SECTION 3:FORMS OF TENDER, AND QUALIFICATION INFORMATION

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

TABLE OF FORMS:

- **FORM OF TENDER**
- **QUALIFICATION INFORMATION**
- **LETTER OF ACCEPTANCE**
- **NOTICE TO PROCEED WITH THE WORK**
- **AGREEMENT FORM**

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Form of Tender

NA

Qualification Information

The information to be filled in by the Tenderer hereunder will be used for purposes of computing Tender capacity as provided for in Clause 3 of the Instructions to Tenderers. This information will not be incorporated in the Contract.

1.1 NA

1.2 Total value of Horticultural work works executed and payments received in the last five years (in Rs. Lakh)

2019-20[1]_____
2020-21_____
2021-22_____
2022-23_____
2023-24_____

Or
Documents pertaining to retired horticulture officer or horticulture degree certificate

1.3 NA.

(A) NA
(B) NA
1.4. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer.

[1] Change the years appropriately

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Letter of Acceptance

(letterhead paper of the Employer)

.....[date]

To: .....
[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated: ..... for execution of the ..... [name of the contract and identification number, as given in the Instructions to Tenderers] for the Contract Price of Rupees.....
(.....) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit, in the form detailed in Para 24.1 of ITT for an amount of Rs..... within 07 days of the receipt of this letter of acceptance valid up to 30 days from the date of expiry of Maintainance period i.e. up to ..... and sign the contract, failing which action as stated in Para 24.3 of ITT will be taken.

Yours faithfully,

Authorized Signature

Name and Title of Signatory

Name of Agency

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Issue of Notice to proceed with the work

(letter head of the Employer)

…… (date)

To

———————————————— (name and address of the Contractor)

————————————————

————————————————

Dear Sirs:

Pursuant to your furnishing the requisite Security deposit as stipulated in ITT Clause 24.1 and signing of the contract agreement for the construction of …… *(name of the work)*a Tender Price of Rs……., you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,
(Signature, name and title of signatory
Authorized to sign on behalf of Employer)

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Agreement Form

Agreement

This agreement, made the .....day of .....20 ....., between.....
[name and address of Employer]
(herein after called "the Employer") of the one part and .....
.....
..... [name and address of contractor] (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor .....
.....
.....[name and identification number of Contract] (hereinafter called "the Works") and the Employer has accepted the Tender by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a contract price of Rupees.....

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
   i) Letter of Acceptance;
   ii) Notice to proceed with the works;
   iii) Contractor's Tender;
   iv) Contract Data;
   v) Conditions of contract (including Special Conditions of Contract);
   vi) Specifications;
   vii) Drawings;
   viii) Bill of Quantities; and
   ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.
The Common Seal of
.....
was hereunto affixed in the presence of:

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Signed, Sealed and Delivered by the said
……
……
in the presence of:
Binding Signature of Employer
……

Binding Signature of Contractor…..
……

SECTION 4: CONDITIONS OF CONTRACT

Table of Contents

A.	**General**	**Page No.**
	1. Definitions	24
	2. Interpretation	25
	3. Law governing contract	25
	4. Employers decisions	25
	5. Delegation	25
	6. Communications	25
	7. Subcontracting	25
	8. Other Contractors	25
	9. Personnel	26
	10. Employer’s and Contractor’s risks	26
	11. Employer’s risks	26
	12 Contractor’s risks	26
	13 Query about Contract Data	26
	14 Contractor to construct the Works	26
	15. The Works to be completed by Intended Completion Date	26
	16. Safety	26
	17. Discoveries	26
	18. Possession of the Site	27
	19. Access to the Site	27
	20. Instructions	27
B.	**Time Control**	
	21. Program	27
	22. Extension of the Intended Completion Date	27
	23. Delays ordered by the Employer	27

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

24. Management meetings 27

C. Quality Control

25. Identifying defects 28
26. Tests 28
27. Correction of defects 28
28 Uncorrected defects 28

D. Cost Control

29 Bill of Quantities (BOQ) 28
30 Variations 28
31. Payment for Variations 29
32. Submission of bills for payment 29
33 Payments 29
34. Compensation events 29
35. Tax 29
36. Liquidated damages 29
37. Cost of repairs 30

E Finishing of Contract

38. Completion 30
39. Taking Over 30
40. Final account 30
41. As built drawings 30
42. Termination 30
43 Payment upon termination 31
44. Property 31
45. Release from performance 31

F Special Conditions of Contract 32

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

A. General

1. Definitions

1.1 Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Bold letters are used to identify defined terms.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Tender.
Compensation events are those defined in Clause 34 hereunder.
The **Completion Date** is the date of completion of the Works as certified by the Employer in accordance with Sub Clause 38.1.
The **Contract** is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.3 below.
The **Contract Data** defines the documents and other information which comprise the Contract.
The **Contractor** is a person or corporate body whose Tender to carry out the Works has been accepted by the Employer.
The **Contractor's Tender** is the completed Tender document submitted by the Contractor to the Employer.
The **Contract price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.
Days are calendar days; **months** are calendar months.
A **Defect** is any part of the Works not completed in accordance with the Contract.
The **Defects liability period** is the period named in the Contract Data and calculated from the Completion Date.
The **Employer** is the party who will employ the Contractor to carry out the Works.
Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works.
The **Initial Contract price** is the Contract Price listed in the Employer's Letter of Acceptance.
The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the Contract Data. The Intended Completion Date may be revised only by the Employer by issuing an extension of time.
Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.
Plant is any integral part of the Works which is to have a mechanical, electrical, electronic or chemical or biological function.
The **Site** is the area defined as such in the Contract Data.
Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Employer.
The **Start Date** is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Dates.

Senior Assistant Director of
Horticulture
Bengaluru west City
Corporation
Zone-2, Malleshwaram

A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.
A **Variation** is an instruction given by the Employer which varies the Works.
The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the Contract Data.

2. Interpretation

2.1 In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Employer will provide instructions clarifying queries about the Conditions of Contract.

2.2 The documents forming the Contract shall be interpreted in the following order of priority:

(1) Agreement
(2) Letter of Acceptance, notice to proceed with the works
(3) Contractor's Tender
(4) Contract Data
(5) Conditions of Contract
(6) Specifications
(7) Drawings
(8) Bill of quantities and
(9) any other document listed in the Contract Data as forming part of the Contract.

3. Law governing contract

3.1 The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

4.1 Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. Delegation

5.1 The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

6.1 Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting

7.1 Deleted

Senior Assistant Director of
Horticulture
Bengaluru west City
Corporation
Zone-2, Malleshwaram

8. Other Contractors

8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

9.1 The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.

9.2 If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. Employer's risks

11.1 The Employer is responsible for the excepted risks which are (a) in so far as rebellion, riot commotion or disorder or (b) a cause due solely to the design of the Works, other than the Contractor's design.

12. Contractor's risks

12.1 All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Queries about the Contract Data

13.1 The Employer will clarify queries on the Contract Data.

14. Contractor to construct the Works

14.1 The Contractor shall construct the Works in accordance with the Specification and Drawings.

15. The Works to be completed by the Intended Completion Date

15.1 The Contractor may commence execution of the Works on the Start Date and complete them by the Intended Completion Date.

16. Safety

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

16.1 The Contractor shall be responsible for the safety of all activities on the Site.

17. Discoveries

17.1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

18. Possession of the Site

18.1 The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

19. Access to the Site

19.1 The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

20. Instructions

20.1 The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

B. Time Control

21. Program

21.1 Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.

21.2 The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

22. Extension of the Intended Completion Date

22.1 The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.

22.2 The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

Senior Assistant Director of
Horticulture
Bengaluru west City
Corporation
Zone-2, Malleshwaram

23. Delays ordered by the Employer

23.1 The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

24. Management meetings

24.1 The Employer may require the Contractor to attend a management meeting. The business of a management meeting shall be to review the progress achieved and the plans for remaining work.

24.2 The responsibility of the parties for actions to be taken is to be decided by the Employer either at the management meeting or after the management meeting and stated in writing to be distributed to all who attended the meeting.

C. Quality Control

25. Identifying defects

25.1 The Employer shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Employer may instruct the Contractor to search for a Defect and to uncover and test any work that the Employer considers may have a Defect

26. Tests

26.1 If the Employer instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect the test shall be a Compensation Event.

27. Correction of defects

27.1 The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.

27.2 Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer’s notice.

28. Uncorrected defects

28.1 If the Contractor has not corrected a Defect within the time specified in the Employer’s notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

29. Bill of Quantities (BOQ)

29.1 The BOQ shall contain items described .

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

29.2 The BOQ is used to calculate the Contract Price.

30. Variations

30.1 NA

30.2 The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.

30.3 NA

30.4 The Contractor shall promptly request in writing to the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing within 30 days, failing which the work shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BWCC has to be obtained for the variation exceeding 5%.

31. Payments for Variations

31.1 NA

31.2 NA

31.3 NA

31.4 NA

31.5 NA

31.6 NA

31.7 NA

32. Submission of bills for payment

32.1 The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.

32.2 The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.

32.3 The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

33. Payments

33.1 NA

33.2 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

34. Compensation events

34.1 NA

.

34.2 NA

34.3 NA

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

34.4 NA

35. Tax

35.1 The rates quoted by the Contractor shall be deemed to be inclusive of the sales and other taxes that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

36. Liquidated damages

36.1 NBA
36.2 NA

37. Cost of repairs

37.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

38. Completion

38.1 The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

39. Taking over

39.1 The Employer shall take over the Site and the Works within seven days of issuing a certificate of Completion.

40. Final account

40.1 NA

41. As built drawings

41.1 NA
41.2 NA

42. Termination

42.1 The Employer or the Contractor may terminate the Contract if the other party causes a fundamental breach of the Contract.
42.2 Fundamental breaches of Contract include, but shall not be limited to the following:
(a) the Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;
(b) Deleted

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

(c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;
(d) Deleted
(e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;
(f) the Contractor does not maintain a security which is required;
(g) NA
(h) if the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.
For the purpose of this paragraph : "corrupt practice" means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution. "Fraudulent practice" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition."

42.3 When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under Sub Clause 42.2 above, the Employer shall decide whether the breach is fundamental or not.

42.4 Notwithstanding the above, the Employer may terminate the Contract for convenience.

42.5 If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

43. Payment upon Termination

43.1 If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.

43.2 If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

44. Property

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

44.1 All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

45. Release from performance

45.1 If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made.

F. Special Conditions of Contract

1. **Labour :**

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the site and such other information as the Employer may require.

2. **Compliance with labour regulations** :

During continuance of the contract, the Contractor and his sub contractors shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor and the Sub-Contractor in no case shall be treated as the employees of the Employer at any point of time.

Senior Assistant Director of
Horticulture
Bengaluru west City
Corporation
Zone-2, Malleshwaram

3. **Protection of Environment:**

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor and his sub-contractors shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work.

5. The successful bidder should furnish the difference of amount (ie., difference of Estimated cost and Quoted amount) if quoted below the CSR in the form of D.D in favour of the Chief Commissioner before entering to Agreement

6.

[Add other Clauses specific to the work for which tenders are invited.]

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

SECTION 5: CONTRACT DATA

NA

SECTION 6: SPECIFICATIONS

As per the specifications mentioned in the BOQ**SECTION 7: DRAWINGS**

NA

SECTION 8: BILL OF QUANTITIES (BOQ)

Sl. No.	Description of Items	Nos		Length in mtrs	Breadth in mtrs	Depth in mtrs	Quantity	units	Rate in Rs	Total Amount in Rs
					PART-A					
1	Dismantling tile work in floors and roofs laid in cement mortar includ- ing stacking material to the appropriate disposal area as per direction of Engineer-in-charge.For thickness of tiles 10 mm to 25 mm									
	P.NO.189 I.NO.19.22.1 KPWD SR 2023.24 VOL-2									
	swimming pool park path way damaged tiles	1	1	2.00	2.20		4.40			
		1	3	3.00	2.20		19.80			
		1	1	1.00	2.20		2.20			
	Basic Rate 48.00						26.40	sqm	52.80	1,393.92
	10% Area weightage 4.80									
	Toatal 52.80									
2	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge.									
	P.NO.187 I.NO.19.2.1 KPWD SR 2023.24 VOL-2									
	Pathway damaged concrete	1	1	2.00	2.20	0.15	0.66			

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

			1	3	3.00	2.20	0.15	2.97			
			1	1	1.00	2.20	0.15	0.33			
	Basic Rate	1,663.00						3.96	cum	1,829.30	7,244.03
	10% Area weightage	166.30									
	Toatal	1,829.30									
3	Removal of stumps and roots including backfilling with suitable material to required compaction (i)Girth from 300 mm to 600 mm										
	P.NO. 9 I.NO.2.2(201) b KPWD VOL-3 SR 2023.24										
	swimming pool park path way		1	6				6.00			
	Basic Rate	356.00						6.00	each	391.60	2,349.60
	10% Area weightage	35.60									
	Toatal	391.60									
4	Earth work excavation by manual means for drains,canals ,waste weir,draft,approch channels ,key trenchs ,foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, re- moval of stumps and other deleterious matter, excavated surface lev- eled and sides neatly dressed disposing off the excavated stuff or sort- ing & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work In all kinds of soils Depth upto 1.5 m										
	P.NO.5 I.NO.1.4.1 VOL-1 P.W.D .CSR 2023-24										
	RCC sump		1	1	3.50	2.50	2.10	18.38			
	Basic Rate	242.00						18.38	cum	266.20	4,891.43
	10% of Area Weightage	24.20									
	Toatal	266.20									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

5	Lead for Disposal of Earth &Debries shall be payable including loading unloading up to 15Kms											
	qty.same as in item no 1			26.40				0.05	1.32			
	qty.same as in item no 2								3.96			
	qty.same as in item no 4						18.38					
	(i)Cost of Haulage,excluding loading and unloading case-1 surface load						**23.66**	cum	168.30			3,981.14
	(a)Taking output 10 t load and lead 10 km = 100 t.km P.NO.5 I.NO.1.4 KPWD SR 2023-24	12.00		For 10Kms =12t.km								
				For 15Kms=(12x15)/10=18 Rs								
	Cost of Hauling for 15KM	18.00										
	Loading and Unloading of Stone Boulder/Stone aggregates/Sand/ Kankar/Moorum. (Tipper 5.5 m) P.NO.5 I.NO.1.1 (a) KPWD SR 2023-24	135.00										
	Sub Total Rate Rs	153.00										
	Area Weightage at 10%	15.30										
	Total Rate	168.30										

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

6	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately Mix 1:3:6 (M10) Using 40 mm and down size graded crushed coarse aggregates											
	P.NO.15 I.NO.2.1.3 VOL-1 P.W.D .CSR 2023-24											
	Pathwayconcrete		1	1	2.00	2.20	0.15	0.66				
			1	3	3.00	2.20	0.15	2.97				
			1	1	1.00	2.20	0.15	0.33				
	RCC sump		1	1	3.50	2.50	0.15	1.31				
	Basic rate	5,989.0						5.27	cum	6,587.90	34,734.70	
	10% Area weightage	598.90										
	Total	6,587.9										
7	Providing, laying & fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification											
	P.NO. 65 I.NO.9.40 KPWD VOL-2 SR 2023.24											
	swimming pool park path way tiles		1	1	2.00	2.20		4.40				
			1	3	3.00	2.20		19.80				
			1	1	1.00	2.20		2.20				
	Basic Rate	932.00						26.40	sqm	1,025.20	27,065.28	
	10% Area weightage	93.20										
	Toatal											

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

		1,025.20										
8	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces											
	P.NO.66 I.NO.8.10 VOL.3 SR 2023.24											
	Kerb paint											
	Swimming pool park vijayanagara ward no147 Hampinagara Left side		1	2	83.00		0.35	58.10				
	SWD side		1	1	64.00		0.35	22.40				
	right side		1	2	70.00		0.35	49.00				
	GYM Entrance		1	2	5.00		0.35	3.50				
	Gezebo entrance		1	2	3.80		0.35	2.66				
	sump- side		1	2	3.00		0.35	2.10		i		
	Corner gate side		1	2	11.20		0.35	7.84				
	Basic rate	109.00						145.60	sqm	119.90	17,457.44	
	10% Area Weightage	10.90										
	Total	119.90										
9	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm and down size graded crushed coarse aggregates											
	P.NO.15 I.NO .2.2.3.1 VOL-1 SR-2023-24											
	Bottam Slab		1	1	3.50	2.50	0.20	1.75				
	Long Wall		1	2	3.50	0.20	2.00	2.80				

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	Short Wall		1	2	2.10	0.20	2.00	1.68			
	Top slab		1	1	3.50	2.50	0.15	1.31			
	Man Hole Deduction		1	-1	0.60	0.60	0.15	-0.05			
								7.49	cum	11,151.36	83,506.96
	Basic Rate	6,336.00									
	P.NO.112 VOL-1 SL.NO.14Formwork 60%	3,801.60									
	Sub total	10,137.60									
	10% Area Weigthage	1,013.76									
	Total	11,151.36									
10	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge										
	.(Vol-I P.No-41 I.No-8.2.1 CSR-2023-24)										
	For Internal wall Plastering		1	1	10.40		2.00	20.80			
	Bottam		1	1	3.10	2.10		6.51			
								27.31	sqm	324.50	8,862.10
	Basic Rate	295.00									
	10% Area Weigthage	29.50									
	Total	324.50									
11	Providing 12 mm cement plaster finished with a floating coat of neat cement of mix :1:3 (1 cement: 3 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.										
	.(Vol-II P.No-41 I.No-8.4.1 CSR-2023-24)										
	ceiling Plastering		1	1	3.10	2.10		6.51			
								6.51	sqm	355.30	2,313.00
	Basic Rate	323.00									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	10% Area Weigthage	32.30									
	Total	355.30									
12	UGT/OHT (inside) waterproofing with Anti-microbial Coating Providing and Applying two component, water-based food grade epoxy resin coating on inside surface of Potable water tank having anti-algae, antifungal, Non-toxic, hygiene cum damp-proof coating Certified by CFTRI as per 21 CFR 175 – 300 of US – FDA, having mixing Ratio (Base: Hardener: Water) – 1:1:1 to be applied @ 0.35 Kg/m2 in 2 coats. Ensure that this coating is applied over the protective plaster, and that Item No. 4 is completed across the entire surface prior to applying the protective plaster. The Waterproofing material shall have Specific Gravity: 1.2, Water vapor permeance: 244.48 g/m2/24 hrs, as per IS 7809/Pt 2/1977, Adhesion strength: 2 N/mm2 as per ASTM D 4541: 02. The finished cost to include surface preparation completely as per specification.										
	(Vol-II P.No-152 I.No-15.14 CSR-2023-24)										
	Same as Inside Plastering Qty							27.31			
								27.31	sqm	1,840.30	50,258.59
	Basic Rate	1,673.00									
	10% Area Weigthage	167.30									
	Grand Total	1,840.30									
13	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.a. Buildings										
	(Vol-II P.No-18 I.No-2.11a CSR-2023-24)										
	80 Kg/cum				80	7.49		599.08			
						Total Qty		599.08			
						Total Qty		0.60	MT	98,402.70	58,951.09
	Basic Rate	89,457.00									
	10% Area Weigthage	8,945.70									
	Total	98,402.70									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

14	Providing and fixing MS inspection door of size 60 cms x 60 cms, including MS frame made of 50x50x6mm angle, shutters made of 3mm thick MS sheets, with hinges, locking arrangements at top etc. including painting with anticorrosive approved paint etc. complete including all lead and lifts etc.											
	(Vol-V P.No-85 I.No-7.3 CSR-2023-24)											
			1	1				1.00				
								1.00	each	2,354.00		2,354.00
	Basic Rate	2,140.00										
	10% Area Weigthage	214.00										
	Total	2,354.00										
15	Ladder inside the container: Providing anodized aluminium ladder using 65mm x 32mm x 3.0mm 'C' section for ladder side channel x 25mm dia., flutal pipe for Rungs at 250mm c/c ladder fixed at an angle of 70 degrees to horizontal including necessary 25mm dia., G.I. shutters with necessary G.I. fasteners for bracing the ladders to the Tank walls to prevent buckling of the ladder with necessary (M-15) bed for embedding the ladder bottom complete **aluminium ladder**											
	(Vol-V P.No-88 I.No-7.12.1 CSR 2023-24)											
			1	1	1.00			1.00				
								1.00	mtr	5,610.00		5,610.00
	Basic Rate	5,100.00										
	10% Area Weigthage	510.00										
	Total	5,610.00										
16	Providing, Single Phase Submersible Pump Sets of 100mm dia (4 inch) suitable for bore well confirming to IS 8034-2000 specifications, to work site with testing of as per instructions of engineer incharge of work and latest amendments etc. complete. 5.00 HP/3.7KW 25 STG											
	(Vol V P.No-150 I.No-13.10.1 CSR-2023-24)											
			1	1				1.00				
								1.00	each	29,040.00		29,040.00

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

									00		
	Basic Rate	26,400.00									
	10% Area Weigthage	2,640.00									
	Total	29,040.00									
17	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm										
	(Vol V P.No-157 I.No-13.24.1 CSR-2023-24)										
			1	1				1.00			
								1.00	each	1,375.00	1,375.00
	Basic Rate	1,250.00									
	10% Area Weigthage	125.00									
	Total	1,375.00									
18	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm										
	(Vol V P.No-157 I.No-13.25.1 CSR-2023-24)										
			1	1				1.00			
								1.00	each	1,375.00	1,375.00
	Basic Rate	1,250.00									
	10% Area Weigthage	125.00									
	Total	1,375.00									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

19	Supply, installing,testing and commissioning COMMON control panel consisting of the following INCOMING:1 No set of Phase indicating lamps with SFU of suitable rating 1 No, Analog Ammeter, 1 No Analog Voltmeter 1ni with Phase selector switch, Isolating switch OUTGOING for Main Electrical Pump: 1 No. MCB 1 No. DOL of S/D Starter suitable for respective HP 1 No. Electrcal Protection Like single Phase preventor, under voltage over Volage, under current over current & dry run protection suitable for the pump described above 1 no **for outdoor** type NOTE: 1) DOL-Direct Online Starter 2) S-D- Star Delta Starter etc. complete. **Upto 3 to 6 HP pumps**											
	(Vol V P.No-155 I.No-13.24.2 CSR-2023- 24)											
			1	1				1.00				
								1.00	each	10,505.00	10,505.00	
	Basic Rate	9,550.00										
	10% Area Weigthage	955.00										
	Total	10,505.00										
20	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments. **1x3x6.0 Sqm**											
	(Vol V P.No-155 I.No-13.22.4 CSR-2023-24)											
			1	1	40.00			40.00				
								40.00	mtrs	203.50	8,140.00	
	Basic Rate	185.00										
	10% Area Weigthage	18.50										
	Total	203.50										
	BORE WELL											

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

21	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 isallowed for drilling in overburden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of over burden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test											
	P.NO.140 it no. 12.4 PWD SR 2023-24 VOLUMN-5											
	Basic rate	5,288.00										
	Area weightage of 10%	528.80										
	Total	5,816.80										
	Swimming pool park vijayanagara ward no147		1	1				1.00	each	5,816.80	5,816.80	
22(a)	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete) **Borewell depth of 0 to 50 m**											
	PAGE NO 139 it.no.12.1.1 PWD SR 2023-24 VOLUMN-V											
	Basic rate	370.00										
	Area weightage of 10%	37.00										
	Total	407.00										

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	Swimming pool park vijayanagara ward no147	1	1	50.00			50.00	mtrs	407.00	20,350.00
b	Borewell depth of 50 to100m									
	PAGE NO 139 it.no.12.1.2 PWD SR 2023-24 VOLUMN-V									
	Basic rate 464.00									
	Area weightage of 10% 46.40									
	Total 510.40									
	Swimming pool park vijayanagara ward no147	1	1	50.00			50.00	mtrs	510.40	25,520.00
c	Borewell depth of 100 to 150 m									
	PAGE NO 139 it.no.12.1.3 PWD SR 2023-24 VOLUMN-V									
	Basic rate 493.00									
	Area weightage of 10% 49.30									
	Total 542.30									
	Swimming pool park vijayanagara ward no147	1	1	50.00			50.00	mtrs	542.30	27,115.00
d	Borewell depth of 150 to 200 m									
	PAGE NO 139 it.no.12.1.4 PWD SR 2023-24 VOLUMN-V									
	Basic rate 572.00									
	Area weightage of 10% 57.20									
	Total 629.20									
	Swimming pool park vijayanagara ward no147	1	1	50.00			50.00	mtrs	629.20	31,460.00
e	Borewell depth of 200 to 250 m									
	PAGE NO 139 it.no.12.1.5 PWD SR 2023-24 VOLUMN-V									
	Basic rate 671.00									
	Area weightage of 10% 67.10									
	Total 738.10									
	Swimming pool park vijayanagara	1	1	50.0			50.00	mtrs	738.10	36,905.00

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	ward no147			0							
f	Borewell depth of 250 to 300 m										
	PAGE NO 139 it.no.12.1.6 PWD SR 2023-24 VOLUMN-V										
	Basic rate	740.00									
	Area weightage of 10%	74.00									
	Total	814.00									
	Swimming pool park vijayanagara ward no147		1	1	50.00			50.00	mtrs	814.00	40,700.00
23	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes allshall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar-Medium duty.										
	page no 143 it .no 12.32 PWD SR 2023-24 VOLUMN-V										
	Basic rate	1,933.00									
	Area weightage of 10%	193.30									
	Total	2,126.30									
	Swimming pool park vijayanagara ward no147		1	1	36.50			36.50	mtrs	2,126.30	77,609.95
24	PVC Pipes of 6kg/sqcm forPVC pipes 200mm dia., 6 kg/sqcm & class 3										
	Page no 113 I.NO.10.1.10 PWD SR 2023-24 Volumn-v										
		mtrs									
	Basic rate	1,115.00									
	Area weightage of 10%	111.50									
	Total	1,226.50									
	Swimming pool park vijayanagara ward no147		1	1	18.00			18.00	mtrs	1,226.50	22,077.00

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

25	Providing and laying at site of work MS casing caps as per IS 1239 (partII) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge											
	P.NO.143 I.NO.12.34 PWD SR 2023-24 VOLUMN -V											
	Basic rate	164.00										
	Area weightage of 10%	16.40										
	Total	180.40										
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	180.40		180.40
26	Providing and fixing MS casing collars as per IS 1239 (part-II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments											
	P.NO 143 I.NO 12.33 PWD SR 2023-24 VOLUMN -V											
	Basic rate	150.00										
	Area weightage of 10%	15.00										
	Total	165.00										
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	165.00		165.00
27	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. For 10 HP - 90 LPM @ 220 m = 20 STG Outlet Dia - 2.00”											
	P.NO.152 I.NO13.16.7 PWD SR 2023-24 VOLUMN -V											
	Basic rate	##########										
	Area weightage of 10%	5,461.20										
	Total	##########										
	Swimming pool		1	1					nos			60,073.20

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	park vijayanagara ward no147							1.00		60,073.20		
28	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) -50MM											
	P.NO 155 I.NO 13.27.1 PWD SR 2023-24 VOLUMN -V											
	Basic rate	3,050.00										
	Area weightage of 10%	305.00										
	Total	3,355.00										
	Swimming pool park vijayanagara ward no147		1	46.6				46.60	each length	3,355.00	156,343.00	
29	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges,tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work											
	P.NO.156.SL NO 13.32 PWD SR 2023-24 VOLUME-5											
	Swimming pool park vijayanagara ward no147		1	1				1.00	job	7,150.00	7,150.00	
	Basic rate	6,500.00										
	Area weightage of 10%	650.00										
	Total	7,150.00										
30	Labour charges for erection of outdoor type panel board and meter board units with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions of engineer incharge of work.P.NO.156.SL NO 13.34 PWD SR 2023-24 VOLUME-5											
	P.NO.156.SL NO 13.34 PWD SR 2023-24 VOLUME-5											
	Swimming pool park vijayanagara ward no147		1	1				1.00	job	1,595.00	1,595.00	
	Basic rate	1,450.00										
	Area	14										

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	weightage of 10%	5.00									
	Total	1,595.00									
31	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments 1x3x6 Sqm.										
	P.NO.154 I.NO.13.22.4 KPWD SR-2023-24 VOL-V										
	Basic rate	185.00									
	Area weightage of 10%	18.50									
	Total	203.50									
	Swimming pool park vijayanagara ward no147		1	2	300.00			600.00	mtrs	203.50	122,100.00
32	Providing wrought mild steel (galvanized) 50 mm dia GI collar confirming to IS 1239-II, 1991 with latest amendments if any										
	.P.NO.129 I.NO 11.6.6 PWD SR 2023-24 VOLUMN -V										
	Basic rate	267.00									
	Area weightage of 10%	26.70									
	Total	293.70									
	Swimming pool park vijayanagara ward no147		1	46				46.00	nos	293.70	13,510.20
33	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments										
	P.NO 154 I.NO13.25.1 PWD SR 2023-24 VOLUMN -V										
	Basic rate	1,250.00									
	Area weightage of 10%	125.00									
	Total	1,375.00									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	1,375.00	1,375.00
34	Supplying of on load change over switches 4 poles AC -230A Duty ,415V 50Hz AC supply -100amps (SM Enclosure Sheet Metal Execution)										
	P.No.15 SL.NO 5.12.2 PWD Electrical SR 2023-24										
	Basic rate	8,53									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

		4.00									
	Area weightage of 10%	85 3.40									
	Total	9,38 7.40									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	9,387.40	9,387.40
35	Supplying of TSPT with rewirable porcelain channels in SM encloser made out of 15SWG Powder coated point approved colours 32amps										
	P.NO 14 I.NO 5.5.1 PWD Electrical SR 2023-24										
	Basic rate	1,70 1.00									
	Area weightage of 10%	17 0.10									
	Total	1,87 1.10									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	1,871.10	1,871.10
36	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor Above 12.5 HP upto 25 HP										
	P.NO 14 I.NO 5.2.2 PWD E lectrical SR 2023-24										
	Basic rate	8,76 4.00									
	Area weightage of 10%	87 6.40									
	Total	9,64 0.40									
	Swimming pool park vijayanagara ward no147		1	1				1.00	each	9,640.40	9,640.40
37	Erection of single phase preventer / ammeters / including fixing selector switch / voltmeter / current operated earth leakage circuit breakers / voltage operated circuit breaker / above 100A fuse channel set (3 Nos) HRC fuses above100A (3 Nos.) / Digital ammeter/digital volt meter/set of3 indicating lA /MCB / Relays /A-V selector switches including wiring using suitable capacity wires, bolts, nuts, screws.										
	P.NO.57 I.NO.13.16 PWD Electrical SR -2023-24										
	Basic rate	19 8.00									
	Area	1									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	weightage of 10%	9.80									
	Total	21 7.80									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	217.80	217.80
38	Fabricating supplying and mounting MS box made out .16..SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clA with necessary cable entry pipe with gland and box should be finished with 7 tanks treatment with powder coated paint and finally finished with approved colour etc., complete.										
	P.NO.20 I.NO 5.42.2 PWD Electrical SR -2023-24										
	Basic rate	0.43									
	Area weightage of 10%	0.04									
	Total	0.47									
	Swimming pool park vijayanagara ward no147		1	1	30,0 00			30,000.0 0	sqc m	0.47	14,190.00
39	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32 A TPN										
	P.NO.13 I.NO.5.18.7 PWD Electrical SR 2023-24										
	Basic rate	1,71 7.00									
	Area weightage of 10%	17 1.70									
	Total	1,88 8.70									
	Swimming pool park vijayanagara ward no147		1	1				1.00	each	1,888.7 0	1,888.70
40	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.4 mm2										
	P.NO.5 I.NO 2.3.4 PWD Electrical SR 2023-24										
	Basic rate	6 3.00									
	Area weightage	6.30									

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	of 10%										
	Total	6 9.30									
	Swimming pool park vijayanagara ward no147		1	1	20.00			20.00	mtrs	69.30	1,386.00
41	Supplying, fixing and wiring heavy duty low voltage capacitors conforming to IS 2834. 3 phase, 400/440 V grade, for power factor improvement of rotating machineries like induction motor.										
	P.NO.19 I.NO 5.37 PWD Electrical SR 2023-24										
	Basic rate	48 0.00									
	Area weightage of 10%	4 8.00									
	Total	52 8.00									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	528.00	528.00
42	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.63 A										
	P.NO.14 I.NO 5.7.3 PWD Electrical SR -2023-24										
	Basic rate	40 1.00									
	Area weightage of 10%	4 0.10									
	Total	44 1.10									
	Swimming pool park vijayanagara ward no147		1	3				3.00	nos	441.10	1,323.30
43	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 230/440VAC. 50 Hz 12/24V D.C.										
	P.NO.19 I,NO.5.38 PWD ElectricalSR - 2023-24										
	Basic rate	51 5.00									
	Area weightage of 10%	5 1.50									
	Total	56 6.50									
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	566.50	566.50

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

44	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cut-out with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.600 mm x 600 mm x 170 mm											
	P.NO.16 I.NO 5.44.4 PWD Electrical SR -2023-24											
	Basic rate	########										
	Area weightage of 10%	1,452.00										
	Total	########										
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	15,972.00	15,972.00	
45	Supply and delivery at site GM (copper alloy) gate valves confirming to Class-I as per IS 778 with latest amendments, 1 No. screwed in bonnet inside screw, rising spring spindle integral seat screwed females ends confirming to IS 554/ 1990 body hydraulically tested 1.5HP seat standard tested 1 HP with IS mark For 50 mm dia GM (Copper alloy) Gate valves											
	P.NO 133 I.NO 11.15.6 PWD SR 2023-24 VOLUMN-V											
	Basic rate	1,688.00										
	Area weightage of 10%	168.80										
	Total	1,856.80										
	Swimming pool park vijayanagara ward no147		1	1				1.00	nos	1,856.80	1,856.80	
46	Light duty GI PIPE of 50MM DIA											
	P.NO.127 SL NO 11.1.5 PWD SR 2023-24 VOLUME-5											
	Basic rate	442.00										
	Area weightage of 10%	44.20										
	Total	486.20										
	Swimming pool park vijayanagara ward no147		1	1	8.00			8.00	mtrs	486.20	3,889.60	

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

47	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated PVC extruded inner sheath armoured UG LT cable as per IS 1554 (Part -1) or IS 7098 PART-1 Armouring strip thickness in avarage +5% and resistvity 14 Ohms/Kms (Max) as per IS 3975 **16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm)**											
	P.NO.13 .I.NO.32.05 SL.NO.201 ESCOM ELECTRICAL SR 2023-24											
	Basic rate	########										
	Area weightage of 10%	########										
	Total	########										
	Swimming pool park vijayanagara ward no147		1	1	0.04			0.04	mtrs	########	6,241.05	
48	Labour charges for laying of 1.1 KV class UG cable 6 sqmm to 16 sq mm											
	(PWD Electrical SR 2019-20 P.NO.41.NO.6.5.1											
	Basic rate	11.88										
	Area weightage of 10%											
	Total	11.88										
	Swimming pool park vijayanagara ward no147		1	1	40.00			40.00	mtrs	11.88	475.20	
49	Digging of trenches of 0.6x0.5m wide refilling the trench to the required ground level and consolidating etc., complete cutting road surface **IN Hard soil**											
	(PWD Electrical SR 2019-20P.NO.41.I.NO.6.6.2											
	Basic rate	102.00										
	Area weightage of 10%											
	Total	102.00										
	Swimming pool park vijayanagara ward no147		1	1	40.00			40.00	mtrs	102.00	4,080.00	

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

50	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board in the pit. the pit should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per clause 7.3.3 of using 12mm bolts,nuts,washers and check nuts the pipe shall have 16 through holes of 12 mm dia											
	P.NO.157.SL NO 13.39 PWD SR 2023-24 VOLUME-5											
	Basic rate	3,750.00										
	Area weightage of 10%	375.00										
	Total	4,125.00										
	Swimming pool park vijayanagara ward no147		1	1				1.00				
								1.00	nos	4,125.00	4,125.00	
51	Supplying and fixing LT cast iron pot heads suitable for 1.1 K.V. class UG cable filled with necessary bitumin insulating compound complete with terminals, clamps, bolts nuts & washers etc., for 16 sqmm											
	(PWD Electrical SR 19-20 P.NO.42.I.NO.6.10.2											
	Basic rate	27.00										
	Area weightage of 10%											
	Total	27.00										
	Swimming pool park vijayanagara ward no147		1	1				1.00				
								1.00	nos	270.00	270.00	
52	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, including dressing of excavated surfaces, disposing off or leveling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m. Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work In all kinds of soils. Depth upto 1.50m											

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	P.NO.6 N1.NO.1.6.1 KPWD SR-2023-24 VOL-1										
	Basic rate	484.00									
	Area weightage of 10%	48.40									
	Total	532.40									
	Swimming pool park vijayanagara ward no147		1	1	75.00			75.00	mtrs	532.40	39,930.00
53	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, 50mm dia having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 50MMDIA										
	P.NO.123 I.NO 13.33.6 KPWD SR 2023-24 VOLUME-2										
	Basic rate	721.00									
	Area weightage of 10%	72.10									
	Total	793.10									
	Swimming pool park vijayanagara ward no147		1	1	75.00			75.00	mtrs	793.10	59,482.50
										PART-A Sub Total Rs	**1,188,775.17**
					PART-B						
54	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Alpinia purpurata**(60 to 90 cm Ht) Including cost of plant, materials, transporation and handling & planting Cost) (Horticulture Division BBMP SR 2019-20 Page No.8 Item No-16 (23)							clump		100	800.00	80,000.00
55	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Plumeria Pudica** (150cm - 240cm ht) Including cost of plant, materials, transporation and handling & planting Cost) (Horticulture Division BBMP SR 2019-20 Page No.6 Item No-16 (13)							Each		50	1000.00	50,000.00

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

56	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0,021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Rapis Excelsa** (90cm - 1200cm ht) Including cost of plant, materials, transporation and handling & planting Cost) (Horticulture Division BBMP SR 2019-20 Page No.5 Item No-16 (7)	Each	100	1500.00	150,000.00
57	**Shrubs in Groups**				
a	Developing the area for shrubs by digging to a depth of 0.45m, filling 50% with sand [0,0375 Cum], FYM [0.075 Cum], Red earth [0.21], [I.e. in the proportion of 1:2:3] and planting with well established plants (8 plants per sq mtr) exclusive of cost of plants and inclusive of ingredients (Horticulture Division BBMP SR 2019-20 Page No.1 Item No-4(a)	Sqm	550	435.00	239,250.00
b	Cost of the Plant (8 Plants per Sqm) including Transportation and Handling Charges (Horticulture Division BBMP SR 2019-20 Page No.1 Item No-4(b)	Sqm	550	600.00	330,000.00
58	**Sprinkler System:** Providing and fixing of sprinkler system with in the site by using 25mm/10kg,40mm/6kg, 50mm/6kg good quality PVC pipes,ISI marked sprinklers, control valves and fitiings etc, Including excavation and back filling trenches. (Excluding of Providing Borewell , Electrification & pump). As per the specification and direction of the concerned officer. Rates may be quoted as per data rate specific to the field condition. (Horticulture Division BBMP SR 2019-20 Page No.4 Item No-15)	Each	20	4000.00	80,000.00
	TOTAL PART-B Sub Total Rs				**929,250.00**
	TOTAL (PART-A +B)				**2,118,025.17**
	Add 18% GST CHARGES				**381,244.53**
	Micellanious and unforcen charges				**730.30**
	GRAND TOTAL				**2,500,000.00**

SECTION 8: DRAWINGS

[Will be issued to tenderers who visits the site of work along with SADH (West Zone-2)

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

SECTION 9: BILL OF QUANTITIES (BOQ)

(TO BE FILLED IN FINANCIAL BID through online only)

(Rates Excluding GST as published in the KPPP portal)

-

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: _____ *[name of Employer]*
_____ *[address of Employer]*

WHEREAS _____ [name and address of Contractor] (hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. _____ dated _____ to execute_____ [name of Contract and brief description of Works] (hereinafter called "the Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs._____ [amount of guarantee] [29]_Rupees_____ _____[in words], and we undertake to pay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of_____ [amount of guarantee][30] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____

[29] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract
[30] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

Annexure-1

1. Watering: The plants and lawns in the Park/ Median should be watered frequently as depending upon the climate, soil and plant conditions; if sprinklers are made available, it can be used otherwise hose pipe can be used for Watering. Problems regarding pipeline damage during watering/maintenance should be repaired and taken care Tenderers.
2. Transportation -plastic and other inert materials should be removed from the park and must be taken care of. The swept leaf materials should be used for preparation of Compost manure in the Park wherever is possible and the prepared compost manure should be used in the Park. All dead plants, branches & other waste materials should be removed regularly and transported outside the park at the risk of Tenderers. Garbage or leaf material should not be allowed to pile up especially during leaf shedding time. In case of any fire accident/ deaths due to this, concerned Tenderer will be held responsible
3. Clearing of Dust Bins: The dustbins in the park should be cleared every alternate day, the waste should be disposed and handed over to the dry waste collecting vehicle of BWCC.

28 days

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

Annexure-1
Qualification or Mandatory Documents

1	Name of Tender	
2	Phone Number	
3	Email ID	
4	Valid Address Proof Copy	Submitted/Not Submitted
5	**Work Experience Certificate** Single Work done / work Completion certificate of any one work 50% of the tendered amount in last 5 financial years. (i.e 2020-2021,2021-22, 2022-23, 2023-24 & 2024-25)	Documents Attached
		1.
		2.
		3.
6	Details of Licence / Firm Registration	Submitted/Not Submitted
a)	Copy of Valid Labour Registration certificate	Submitted/Not Submitted

62

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

b)	Copy of Valid ESI & PF Details	Submitted/Not Submitted
c)	Copy of Valid GST Registration	Submitted/Not Submitted
d)	Copy of Valid PAN Card	Submitted/Not Submitted
e)	Copy of Income Tax returns for the Year 2022-2023, 2023-24, and 2024-25	Submitted/Not Submitted
7	Annual Turnover Certificate issued from CA with UDIN Number for Three Financial Years (2022-2023, 2023-24, and 2024-25) **ITR with Balance sheet Profit and loss statement** (26AS),	Submitted/Not Submitted
8	Joint Inspection report issued officially from **Assistant Horticulture Officer and SADH**	Submitted/Not Submitted
9	Notarised Copy of Bank guarantee for unbalanced tender.	Submitted/Not Submitted

(Signature of the authorized Signatory, official Seal)

General Terms and Conditions:
1. All the above said rates are inclusive of all Taxes, Service charges and all other Statutory Payments levied under the existing/ amendment / enacted laws during the period of this contract and the client shall perform such duties in regard to the deduction of such tax may lawfully imposed. And should maintain all registers as per the Government orders.
2. And all the above said rates are inclusive of materials, equipment's, other tools required for watering, digging, weeding, pruning, spraying pesticides, monitoring charges /watch and ward and for other works.
3. It is the prime responsibility of the approved Tenderer /Tenderer to take precautionary measures in order to

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram

	safeguard the deployed workers. During the time of work any accident, injuries or death to the workers. The approved Contractor/Tenderer is solely responsible.
4.	In case of subsequent defaults, the Employer may consider termination of contract and penalty should be imposed.
5.	Any other instructions / works as may be issued by officials in charge from time to time.
6.	The Employer reserves the right to accept or reject any tender and to cancel the tender process and reject all tenders at any time prior to award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderers of the grounds for the Employer's action.

Senior Assistant Director of Horticulture
Bengaluru west City Corporation
Zone-2, Malleshwaram